

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
<b>100-1-1- 0</b>				8/18/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders  
 101 Main Street  
 Amherst, NH 03031

Contact Bill Smith  
 Voice Phone 603-555-1212  
 Fax Phone 603-555-1515

## Project

Sample - New System Sample Project  
 141 General Amherst Road  
 Amherst, NH 03031

Ajax Building & Lumber Supply

Take Route 122 North. Left on Boston Post Road, Right on Bloody Brook, 2nd Lot on Left.

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
<b>Phase 2 - Foundation</b>								
1	Base Foun Coating	FC5	3	5Gal		Foundation Coating	15.06	45.18
2	Base Roof Cement	PRC	1	Ea		Plastic Roof Cement	3.75	3.75
3	Base Tar Boy Brush	TBB	1	Ea		Tar Brush And Handle	8.25	8.25
4	Base Vapor Barrier	6M20100	2	Roll		6 Mill Poly 20 x 100'	58.60	117.20
5	Base Footing Drain	4SPVC	7	Ea		4" x 10' Solid PVC Pipe (Sch 10)	4.39	30.73
6	Base Footing Drain	4PPVC	16	Ea		4" x 10' Perf PVC Pipe (Sch 10)	4.39	70.24
7	Base Footing Tee	4YPVC	1	Ea		4" PVC Wye ( Sch 10)	1.48	1.48
8	Base F Coupling	4CPVC	1	Ea		4" PVC Coupling (Sch 10)	1.58	1.58
9	Base Drain Elbow	490PVC	8	Ea		4" 90o Elbow PVC	1.39	11.12
10	Base Footing Paper	RP	2	Roll		Rosin Paper, Roll	8.50	17.00
11	Base Gutter Pipe	4SPVC	31	Ea		4" x 10' Solid PVC Pipe (Sch 10)	4.39	136.09
12	Base Drop Wye	4YPVC	4	Ea		4" PVC Wye ( Sch 10)	1.48	5.92
13	Base Drop 22.5	4225PVC	4	Ea		4" PVC 22.5o Elbow (Sch 10)	1.58	6.32
14	Base Drop Caps	4ECPVC	4	Ea		4" PVC End Cap (Sch 10)	0.69	2.76
15	Base Outflow Wye	4YPVC	2	Ea		4" PVC Wye ( Sch 10)	1.48	2.96
16	Base Couplings	4CPVC	2	Ea		4" PVC Coupling (Sch 10)	1.58	3.16
17	Base Corner Elbows	490PVC	8	Ea		4" 90o Elbow PVC	1.39	11.12
18	Base Radon Pipe	4PADS250	1	Roll		4" x 250' Roll Perf ADS	74.50	74.50
19	Base Radon Tee	4TADS	1	Ea		4" ADS Tee	4.25	4.25
20	Base Found Insul	2TT	78	Ea		2" X 96" T&G Total Wall	8.75	682.50
21	Base Slab Insul	2TT	191	Ea		2" X 96" T&G Total Wall	8.75	1,671.25
22	Base Door	BILCOC	1	Ea		Bilco C Door 1' 7½" x 6' 0" x 4' 7"	269.00	269.00
23	Base Door Ext	BILCO12E	1	Ea		Bilco C Door Extension 12" x 1' 9"	88.25	88.25
24	Base Stringer	BILCOCSS	1	Ea		Bilco C Door Stair Stringer	98.75	98.75
25	Base Stringer Ext	BILCOSSE	1	Ea		Bilco Stair Stringer Extension	59.95	59.95
26	Base Treads	2108PT	6	Ea	2x10x8	Framing .4 CCA, #2&BTR SYP	8.53	51.18

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
100-1-1-0				8/18/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

**Customer**  
 Quality Home Builders

**Project**  
 Sample - New System Sample Project  
 Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
27	Base Scapewel 2	SW266	2	Ea		Bilco Scapewel 2 Tier 66" Wide - 48" Deep	578.00	1,156.00
28	Base Cover 2	SWC266	2	Ea		Bilco Scapewel 2 Tier Cover 66" Wide 41" Deep	339.00	678.00
29	Garage	TVT	2	Ea		Tyvek Seam Tape 2" Width	3.95	7.90
<b>Phase 2 - Foundation</b>							<b>Sub Total</b>	<b>\$5,316.39</b>
<b>Phase 3 - 1st Floor Deck</b>								
30	Exten Joists	21016SF	12	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	168.00
31	Exten Bridging	13ST	3	Ea	1x3x16	Strapping	1.92	5.76
32	Exten DeckPlywood	34TGP	7	Sht	4x8	3/4" Plum CreekT&G Fir Plywood	24.75	173.25
33	Exten Deck Glue	PL400	4	Tube		PL400 Construction Adhesive, Quarts	4.25	17.00
34	1stFL Sill Seal	DSS	4	Ea		Dow Sill Seal	3.92	15.68
35	1st Sill	2616PT	10	Ea	2x6x16	Framing .4 CCA, #2&BTR SYP	10.24	102.40
36	2nd Sill	2616PT	10	Ea	2x6x16	Framing .4 CCA, #2&BTR SYP	10.24	102.40
37	1stFL Sill Shims	CLEAR	1	Bndl		Shakes - Clear Cedar	17.00	17.00
38	Girder Support	9LC	5	Ea	9	9' Lally Column	17.23	86.15
39	1stFL Girder Stock	21016SF	8	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	112.00
40	1stFL Rim Joist	21016SF	10	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	140.00
41	1stFL Joists	21014SF	59	Ea	2x10x14	Framing, Kiln Dried, D4S, Spruce	14.58	860.22
42	1stFL Stairw'lHangr	10DJH	4	Ea		Simpson 2 x 10 Double Joist Hanger	2.05	8.20
43	1stFL Stairw'lHangr	10SJH	2	Ea		Simpson 2 x 10 Single Joist Hanger	1.04	2.08
44	1stFL Firep'lHangr	10DJH	4	Ea		Simpson 2 x 10 Double Joist Hanger	2.05	8.20
45	1stFL Firep'lHangr	10SJH	6	Ea		Simpson 2 x 10 Single Joist Hanger	1.04	6.24
46	1stFL Bridging	13ST	11	Ea	1x3x16	Strapping	1.92	21.12
47	1stFL DeckPlywood	34TGP	30	Sht	4x8	3/4" Plum CreekT&G Fir Plywood	24.75	742.50
48	1stFL Deck Glue	PL400	15	Tube		PL400 Construction Adhesive, Quarts	4.25	63.75
49	Garage TermiteShield	8TS	2	Roll		Termite Shield for 8" Wall	25.00	50.00
<b>Phase 3 - 1st Floor Deck</b>							<b>Sub Total</b>	<b>2,701.95</b>
<b>Phase 4 - 1st Floor Ext. Walls</b>								
50	1stFL ExtWallPlates	2616SF	30	Ea	2x6x16	Framing, Kiln Dried, D4S, Spruce	8.74	262.20
51	1stFL ExtWall Studs	92PC6	221	Ea	2x6	92 5/8" Precut Stud Spruce	2.00	442.00
52	1stFL SpringBoards	2416SF	20	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	112.00
53	Blind Corner Insul	R19UF15	1	Roll		6" x 15 FG Insul UF R19	14.77	14.77
54	1stFL Sheathing	12CDX	48	Sht	4x8	1/2" CDX Fir Plywood	20.45	981.60

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
<b>100-1-1-0</b>				7/28/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders

## Project

Sample - New System Sample Project

Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
55	1stFL Insul Board	1TT	96	Sht		1" X 96" T & G Total Wall	4.25	408.00
56	1stFL Bracing	CB	16	Ea		Steel Corner Bracing	3.95	63.20
57	1stFL Header Stock	21016SF	14	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	196.00
58	1stFL HeaderSpacer	12CDX	4	Sht	4x8	1/2" CDX Fir Plywood	20.45	81.80
59	House Wrap	TYV9	1	Roll		DuPont Tyvek House Wrap 9' x 195'	161.20	161.20
60	1stFL VaporBar Tape	TVT	2	Ea		Tyvek Seam Tape 2" Width	3.95	7.90
<b>Phase 4 - 1st Floor Ext. Walls</b>							<b>Sub Total</b>	<b>2,730.67</b>
<b>Phase 6 - 2nd Floor Deck</b>								
61	2ndFL Rim Joist	21016SF	8	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	112.00
62	2ndFL Joists	21014SF	54	Ea	2x10x14	Framing, Kiln Dried, D4S, Spruce	14.58	787.32
63	2ndFL Bridging	13ST	11	Ea	1x3x16	Strapping	1.92	21.12
<b>Phase 6 - 2nd Floor Deck</b>							<b>Sub Total</b>	<b>920.44</b>
<b>Phase 7 - 2nd Floor Ext. Walls</b>								
64	2ndFL Sheathing	12CDX	37	Sht	4x8	1/2" CDX Fir Plywood	20.45	756.65
65	2ndFL Insul Board	1TT	74	Sht		1" X 96" T & G Total Wall	4.25	314.50
66	2ndFL Bracing	CB	8	Ea		Steel Corner Bracing	3.95	31.60
67	2ndFL ExtWallPlates	2616SF	24	Ea	2x6x16	Framing, Kiln Dried, D4S, Spruce	8.74	209.76
68	2ndFL ExtWall Studs	268SF	184	Ea	2x6x8	Framing, Kiln Dried, D4S, Spruce	3.15	579.60
69	2ndFL SpringBoards	2416SF	16	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	89.60
70	Blind Corner Insul	R19UF15	1	Roll		6" x 15 FG Insul UF R19	14.77	14.77
71	2ndFL House Wrap	TYV9	1	Roll		DuPont Tyvek House Wrap 9' x 195'	161.20	161.20
<b>Phase 7 - 2nd Floor Ext. Walls</b>							<b>Sub Total</b>	<b>2,157.68</b>
<b>Phase 9 - Roof Framing</b>								
72	Exten Ridge	21016SF	2	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	28.00
73	Exten RoofRafter	2810SF	36	Ea	2x8x10	Framing, Kiln Dried, D4S, Spruce	8.07	290.52
74	Exten Valley Rafter	21016SF	4	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	56.00
75	Exten Roof Deck	12CDX	13	Sht	4x8	1/2" CDX Fir Plywood	20.45	265.85
76	Garage Ridge	21026SF	1	Ea	2x10x26	Framing, Kiln Dried, D4S, Spruce	26.00	26.00
77	Garage RoofRafter	2818SF	42	Ea	2x8x18	Framing, Kiln Dried, D4S, Spruce	17.16	720.72
78	Garage Roof Deck	12CDX	27	Sht	4x8	1/2" CDX Fir Plywood	20.45	552.15
79	Main Ridge	21010SF	1	Ea	2x10x10	Framing, Kiln Dried, D4S, Spruce	10.42	10.42
80	Main Common Rftr	2818SF	62	Ea	2x8x18	Framing, Kiln Dried, D4S, Spruce	17.16	1,063.92

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
100-1-1-0				7/28/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders

## Project

Sample - New System Sample Project

Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
81	Main Hip Rafter	21024SF	8	Ea	2x10x24	Framing, Kiln Dried, D4S, Spruce	21.00	168.00
82	Main Roof Deck	12CDX	40	Sht	4x8	1/2" CDX Fir Plywood	20.45	818.00
<b>Phase 9 - Roof Framing</b>							<b>Sub Total</b>	<b>3,999.58</b>
<b>Phase 12 - Exterior Trim</b>								
83	Gable Rakes	188C	1	Ea	1x8x8	Cedar Trim S4S	0.01	0.01
84	Gable Rakes	1816C	4	Ea	1x8x16	Cedar Trim S4S	0.01	0.04
85	Gable Shadow	148C	1	Ea	1x4x8	Cedar Trim S4S	0.01	0.01
86	Gable Shadow	1416C	4	Ea	1x4x16	Cedar Trim S4S	0.01	0.04
87	Facia	11010C	3	Ea	1x10x10	Cedar Trim S4S	0.01	0.03
88	Facia	11016C	14	Ea	1x10x16	Cedar Trim S4S	0.01	0.14
89	Facia Shadow	1410C	3	Ea	1x4x10	Cedar Trim S4S	0.01	0.03
90	Facia Shadow	1416C	14	Ea	1x4x16	Cedar Trim S4S	0.01	0.14
91	Corner Board Wide	168C	4	Ea	1x6x8	Cedar Trim S4S	0.01	0.04
92	Corner Board Wide	1610C	11	Ea	1x6x10	Cedar Trim S4S	0.01	0.11
93	Corner Board Nar	168C	4	Ea	1x6x8	Cedar Trim S4S	0.01	0.04
94	Corner Board Nar	1610C	11	Ea	1x6x10	Cedar Trim S4S	0.01	0.11
95	Frieze Board	168C	1	Ea	1x6x8	Cedar Trim S4S	0.01	0.01
96	Frieze Board	1610C	2	Ea	1x6x10	Cedar Trim S4S	0.01	0.02
97	Frieze Board	1616C	12	Ea	1x6x16	Cedar Trim S4S	0.01	0.12
98	Skirt Board	11212C	1	Ea	1x12x12	Cedar Trim S4S	0.01	0.01
99	Skirt Board	11216C	9	Ea	1x12x16	Cedar Trim S4S	0.01	0.09
100	GarageDoorTrim	1510C	2	Ea	1x5x10	Cedar Trim S4S	0.01	0.02
101	GarageDoorTrim	1516C	2	Ea	1x5x16	Cedar Trim S4S	0.01	0.02
<b>Phase 12 - Exterior Trim</b>							<b>Sub Total</b>	<b>1.03</b>
<b>Phase 13 - Roofing</b>								
102	Ice and Water Shield	BITR	6	Roll		W.R.Grace Ice&Water Shield, Bituthene 75'	78.00	468.00
103	Ridge Vent	RV40	2	Roll		Roll Vent - 40	56.95	113.90
104	Roofing	GAFTL	100	Bndl		GAF Timberline Shingle 30 Yr 4Bdl=1Sq	13.00	1,300.00
105	Roof Caps	GAFTTC	5	Ea		Gaf Timber Tex Cap Shingles	20.00	100.00
106	RoofingFelt	GAFFLT	7	Roll		GAF ShingleMate, Roofing Felt	11.00	77.00
107	Drip Edge	8DEG	31	Ea		8" Drip Edge, Galvanized	2.52	78.12

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
<b>100-1-1- 0</b>				7/28/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders

## Project

Sample - New System Sample Project

Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
108	Starters	GAFS	3	Bndl		GAF Sovereign Shingle 25 Yr 3Bdl=1SQ	8.50	25.50
<b>Phase 13 - Roofing</b>							<b>Sub Total</b>	<b>2,162.52</b>
<b>Phase 14 - Interior 1st Framing</b>								
109	1stFL StairStringer	21214SF	3	Ea	2x12x14	Framing, Kiln Dried, D4S, Spruce	13.60	40.80
110	1stFL Strapping	13ST	58	Ea	1x3x16	Strapping	1.92	111.36
111	1stFL Pl'mbngPlates	2612SF	2	Ea	2x6x12	Framing, Kiln Dried, D4S, Spruce	6.55	13.10
112	1stFL Pl'mbng Studs	268SF	13	Ea	2x6x8	Framing, Kiln Dried, D4S, Spruce	3.15	40.95
113	1stFL BearingPlates	2416SF	7	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	39.20
114	1stFL Int'r Plates	2416SF	18	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	100.80
115	1stFL Int'r Studs	248SF	194	Ea	2x4x8	Framing, Kiln Dried, D4S, Spruce	2.64	512.16
116	2ndFL StairStringer	21214SF	3	Ea	2x12x14	Framing, Kiln Dried, D4S, Spruce	13.60	40.80
117	2ndFL Overlay	2816SF	51	Ea	2x8x16	Framing, Kiln Dried, D4S, Spruce	12.91	658.41
118	2ndFL Strapping	13ST	50	Ea	1x3x16	Strapping	1.92	96.00
119	2ndFL Pl'mbngPlates	2612SF	2	Ea	2x6x12	Framing, Kiln Dried, D4S, Spruce	6.55	13.10
120	2ndFL Pl'mbng Studs	268SF	13	Ea	2x6x8	Framing, Kiln Dried, D4S, Spruce	3.15	40.95
121	2ndFL BearingPlates	2416SF	7	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	39.20
122	2ndFL Int'r Plates	2416SF	19	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	106.40
123	2ndFL Int'r Studs	248SF	194	Ea	2x4x8	Framing, Kiln Dried, D4S, Spruce	2.64	512.16
<b>Phase 14 - Interior 1st Framing</b>							<b>Sub Total</b>	<b>2,365.39</b>
<b>Phase 16 - Exterior Siding</b>								
124	Siding	126CVG	10,251	LinFt		1/2 X 6" Siding CVG Cedar	1.04	10,661.04
<b>Phase 16 - Exterior Siding</b>							<b>Sub Total</b>	<b>10,661.04</b>
<b>Phase 17 - Drywall</b>								
125	Drywall Int Wall	1212SR	117	Sht	1/2x4x12	Sheetrock	8.06	943.02
126	Drywall Ext Wall	1212SR	42	Sht	1/2x4x12	Sheetrock	8.06	338.52
127	Drywall Ceiling	1212SR	41	Sht	1/2x4x12	Sheetrock	8.06	330.46
128	Drywall Gar Wall	5812FCR	3	Sht	5/8x4x12	Firecode Sheetrock	10.50	31.50
129	Drywall Gar Ceiling	5812FCR	12	Sht	5/8x4x12	Firecode Sheetrock	10.50	126.00
130	Drywall Screw	114FDW	2	Ea		1 1/4" Fine Drywall Screw 8M	45.25	90.50
131	Drywall Joint Cmpd	5GBC	18	5Gal		Gold Bond Joint Compound	11.75	211.50
132	Drywall Tape	250PT	11	Roll		Perf-A-Tape 250'	2.19	24.09
133	Drywall Corner Bead	10CRN	22	Ea		10' Corner Bead	2.15	47.30

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
100-1-1-0				11/ 1/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders

## Project

Sample - New System Sample Project

Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
134	Drywall Trim	12EDG	22	Ea		½" x 10' 'J' Drywall Channel	3.45	75.90
<b>Phase 17 - Drywall</b>							<b>Sub Total</b>	<b>2,218.79</b>
<b>Phase 18 - Insulation</b>								
135	Insul Ext Walls	R19KF15	41	Roll		6" x 15 FG Insul KF R19	15.72	644.52
136	Insul Ceiling	R30KF15	19	Roll		9" x 15 FG Insul KF R30	26.02	494.38
137	Insul Gar Ceiling	R19KF15	12	Roll		6" x 15 FG Insul KF R19	15.72	188.64
138	Insul Under Floor	R30UF15	18	Roll		9" x 15 FG Insul UF R30	26.89	484.02
139	Insul Blockers	R19UF15	3	Roll		6" x 15 FG Insul UF R19	14.77	44.31
140	Insul Gar Walls	R13KF15	8	Roll		3½" x 15 FG Insul KF R13	0.01	0.08
141	Insul Proper Vent	PV24	43	Ea		Proper Vent	0.85	36.55
142	Insul Accessories	16IS	6	Box		Insulation Support 16oc-100ct	6.00	36.00
143	Insul Wall Poly	6POLY10	3	Roll		6MIL 10x100 Clear Poly	33.95	101.85
144	Insul Ceiling POLY	6POLY10	1	Roll		6MIL 10x100 Clear Poly	33.95	33.95
145	Insul Staples	38BOS	9	Box		3/8" Bostich Staple	2.69	24.21
<b>Phase 18 - Insulation</b>							<b>Sub Total</b>	<b>2,088.51</b>
<b>Phase 19 - Interior Trim</b>								
146	1stFL Chair Rail	8453FJP	36	LinFt		1 1/16 X 1 1/8" Base FJ Primed	0.55	19.80
147	1stFL Chair Rail	8614FJP	36	LinFt		S 4 S 1 1/16 X 1 3/4 FJ Primed	0.55	19.80
148	1stFL Cellar Rail	O-75	14	LinFt		1 1/2 X 1 3/4" Hand Rail Fir	0.55	7.70
149	1stFL Rail Bracket	HB	3	Ea		Handrail Bracket	1.25	3.75
150	1stFL Stair Ins Dome	1THERM	2	Sht	4x8	1" Therrmax Sheathing	11.75	23.50
151	1stFL Stair Ins Glue	PL400	1	Tube		PL400 Construction Adhesive, Quarts	4.25	4.25
152	1stFL Folding Stair	EX89	1	Ea		Excel 8' 9" Folding Stair	50.00	50.00
153	1stFL Casing	8710FJP	544	LinFt		2 ½" Colonial Casing - Finger Jointed Pine	0.50	272.00
154	1stFL Stool Cap	B668FJP	48	LinFt		2 1/4" Stool Cap FJ Primed	0.55	26.40
155	1stFL Baseboard	8385AFJP	911	LinFt		3 1/2" Colonial Base FJ Primed	0.55	501.05
156	1stFL Crown/Cornice	8004FJP	52	LinFt		5 1/4" Crown Molding FJ Primed	0.55	28.60
157	1stFL Chair Rail	8627FJP	36	LinFt		2 1/2" Chair Rail Casing FJ Primed	0.55	19.80
158	1stFL Linen Cleat	1414PS	4	Ea	1x4x14	Standard Pine D4S	3.20	12.80
159	1stFL Linen Shelf	34PB	2	Sht	4x8	¾" Particle Board	21.60	43.20
160	1stFL Closet Cleat	1416PS	3	Ea	1x4x16	Standard Pine D4S	3.80	11.40
161	1stFL Rod Sockets	CRS	6	Pr		Closet Rod Socket - Plastic	1.19	7.14

# Ajax Building and Lumber Supply C. Inc.

456 South Main Street, Elmira, NY 05555  
 Voice 508-771-7969 FAX 508-775-2799

Quote #	Spec Ver	Quote Ver	Cust	Quote Date
<b>100-1-1-0</b>				11/ 1/1998
This list is an estimate and does not include any representation of fitness for use. Engineering and compliance with local and national building codes or accepted practices are the responsibility of the buyer.				
<b>This quotation is valid until Tuesday, Nov 30 1999</b>				

## Customer

Quality Home Builders

## Project

Sample - New System Sample Project

Ajax Building & Lumber Supply

Line	Purpose	Item	Quan	Unit	Size	Description	Price Ea	Amount
162	1stFL Shelf Support	CSS	5	Ea		Closet Shelf Support	2.29	11.45
163	1stFL Closet Pole	8912	39	LinFt		1 5/16" Closet Pole Fir	0.55	21.45
164	1stFL Closet Shelf	SHELFW	5	Ea		¾ x 11¼ x 97 White Shelving	6.15	30.75
<b>Phase 19 - Interior Trim</b>							<b>Sub Total</b>	<b>1,114.84</b>
<b>Phase 29 - Garage</b>								
165	Garage Sill Seal	DSS	2	Ea		Dow Sill Seal	3.92	7.84
166	Garage Hard'd Nails	MN	2	Lb		3" Case Hardened Masonry Nails	1.31	2.62
167	Garage Corn'rBrace	CB	6	Ea		Steel Corner Bracing	3.95	23.70
168	Garage 1st Sill	2616PT	4	Ea	2x6x16	Framing .4 CCA, #2&BTR SYP	10.24	40.96
169	Garage Wall Plates	2416SF	12	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	67.20
170	Garage Studs	2410SF	66	Ea	2x4x10	Framing, Kiln Dried, D4S, Spruce	3.50	231.00
171	Garage OHDoor Jacks	248PT	4	Ea	2x4x8	Framing .4 CCA, #2&BTR SYP	4.00	16.00
172	Garage Gable Studs	248SF	10	Ea	2x4x8	Framing, Kiln Dried, D4S, Spruce	2.64	26.40
173	Garage SpringBoards	2416SF	8	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	44.80
174	Garage	2416SF	12	Ea	2x4x16	Framing, Kiln Dried, D4S, Spruce	5.60	67.20
175	Garage Solid Header	21016SF	1	Ea	2x10x16	Framing, Kiln Dried, D4S, Spruce	14.00	14.00
176	Garage Header Spacer	12CDX	1	Sht	4x8	1/2" CDX Fir Plywood	20.45	20.45
177	Garage OHDoorHeade	21210SF	2	Ea	2x12x10	Framing, Kiln Dried, D4S, Spruce	11.30	22.60
178	Garage OHDoorHeade	21210SF	2	Ea	2x12x10	Framing, Kiln Dried, D4S, Spruce	11.30	22.60
179	Garage O'Head1Door	97WDH	1	Ea		Garage Door, Wayne Dalton 9' x 7' Hardboard	270.00	270.00
180	Garage O'Head2Door	97WDH	1	Ea		Garage Door, Wayne Dalton 9' x 7' Hardboard	270.00	270.00
<b>Phase 29 - Garage</b>							<b>Sub Total</b>	<b>1,147.37</b>
<b>Additional Items</b>								
181	2ndFL	TVT	2	Ea		Tyvek Seam Tape 2" Width	3.95	7.90
<b>Additional Items</b>							<b>Sub Total</b>	<b>7.90</b>
<b>Grand Total</b>								<b>39,594.10</b>